



## Early Loading to Deploy Overlay Joints: Does It Work?

**Presenter:** Tom Burnham, Senior Road Research Engineer, MnDOT

**Principal Investigator:** Mike Wallace, Concrete Research Scientist, MnDOT

*2022 NCC Spring Meeting*


*4/6/2022*

## Outline

- **Background**
- **Study Objectives**
- **Case Histories**
- **Conclusions**

## Natural Joint Deployment

- Friction resists shrinkage = cracking at sawed joints




4/6/22

3

## Concrete Overlays

- Concrete Overlay on Asphalt (COA)
- Concrete Overlay on Concrete (COC)




4/6/22

4

## Non-Uniform Joint Deployment in COAs

- Dominant joints (sealant bumps)
- Inconsistent faulting patterns
- Increased potential for buckled panels?



4/6/22

5

## Thin Concrete Overlays on Asphalt

- Causes for Joint Deployment Issues
  - Strong early bond to underlying asphalt
  - Many more joints, often formed using “skip” sawing technique

4/6/22

6

## Impact of Traffic?

3/19/2021 Location B (Age: 9 months)		3/19/2021 Location C (Age: 9 months)	
Joint	Deployed?	Joint	Deployed?
0	N	0	Y
1	Y	1	Y
2	N	2	N
3	Y	3	N
4	N	4	N
5	Y	5	N
6	N	6	N
7	N	7	N
8	Y	8	Y
9	N	9	N
10	N	10	N
11	N	11	Y
12	Y	12	Y
13	N	13	Y
14	N	14	N
15	N	15	Y
16	N	16	Y
17	Y	17	N
18	N	18	N
19	N	19	Y
20	N	20	N

4/6/22

7

## Benefit of Deployed Joints

- COAs designed for small panels to reduce warp and curl
- More joints = smaller openings after shrinkage = increased aggregate interlock
- Better long term performance?

4/6/22

8

## Joint Deployment via Early Loading

- **Apply heavier loads earlier to encourage joint deployment**
  - Must be careful not to damage pavement



4/6/22

9

## Early Loading Criteria

- **Timing of load application**
  - Minimum time after saw cutting?
  - Degree of set and hydration of mix (maturity)
  - Mitigate pavement damage
- **Loading configuration**
  - Axle weight
  - Axle spacing
  - Vehicle speed
  - Number of passes
- **Site conditions affect rate of slab shrinkage**
  - Windy weather
  - Extreme changes in temperature

4/6/22

10

## Study Objectives

- Visit COA construction sites where early loading applied
- Document deployment of loaded and unloaded joints
  - Shortly after early loading
  - 1 week, 3 weeks, 6 months, 1 year

4/6/22

11

## Methods




Visual surveys

4/6/22

12

## Methods




Ultrasonic tomography (MIRA device)

4/6/22

13

## Ultrasonic Tomography

### Profile views



4/6/22

14

## Case Histories

### ➤ CSAH 1 (Filmore County, MN)

- 5-inch thick COA on 7-inch thick HMA, constructed in 2020
- 6-foot by 6-foot panel size
- High and low air temperatures during paving were 76°F and 40°F
- 1000-foot stretch of roadway subjected to early loading
- Load vehicle: 3-axle water truck filled to estimated 58,000 lbs total weight
- Two passes of truck approximately 19 and 25 hours after paving
- Maturity of the concrete was 422.4 C-hours at the time of the first pass
- Deployment surveys done @ 1 week, 3 weeks, and 9 months

4/6/22

15

## Joint Deployment Observations – CSAH 1


5/27/2020 Location A (Early Loading)		6/11/2020 Location A (Age: 3 weeks)		3/19/2021 Location A (Age: 9 months)	
Joint	Deployed?	Joint	Deployed?	Joint	Deployed?
17	Y	17	Y	17	Y
28	N	28	N	28	Y
29	Y	29	Y	29	Y
39	N	39	N	39	Y
47	Y	47	Y	47	Y
49	N	49	N	49	N
62	N	62	N	62	Y
64	Y	64	Y	64	Y
74	Y	74	Y	74	Y
75	N	75	N	75	N
84	N	84	N	84	N
89	N	89	N	89	N
93	N	93	N	93	N
95	N	95	N	95	N
97	N	97	N	97	N
105	N	105	N	105	N
107	N	107	N	107	N
108	N	108	N	108	Y
115	Y	115	Y	115	Y
115	N	115	N	115	Y
123	N	123	N	123	N
130	N	130	N	130	N
132	N	132	N	132	N
133	Y	133	Y	133	Y
138	N	138	N	138	Y
139	N	139	N	139	N
143	N	143	N	143	N
148	N	148	N	148	Y
150	N	150	N	150	N
152	N	152	N	152	N
153	Y	153	Y	153	Y
154	N	154	N	154	N
155	N	155	N	155	N

4/6/22

16




## Joint Deployment Observations – CSAH 1



4/6/22

17

## Joint Deployment Observations – CSAH 1



4/6/22

18

## Case Histories

### ➤ CSAH 21 (Filmore County, MN)

- 5-inch thick COA on variable thickness HMA, constructed in 2021
- 6-foot by 6-foot panel size
- High and low air temperatures during paving were 84°F and 45°F
- Entire project subjected to early loading
- Load vehicle: 3-axle water truck filled to estimated 58,000 lbs total weight
- Two passes of approximately 13, 22 and 26 hours after paving
- Maturity of the concrete was 678.9 C-hours at the time of the first pass
- Deployment survey done @ various ages (1 day to 10 days)

4/6/22

19


## Joint Deployment Observations – CSAH 21

Joint	Segment A (Age 10 days) (Loaded approx. 26 hrs. after paving)		Segment B (Age 5 days) (Loaded approx. 22 hrs. after paving)		Segment C (Age 1 day) (Loaded approx. 13 hrs. after paving)	
	Northbound	Southbound	Northbound	Southbound	Northbound	Southbound
0	Y	Y	Y	Y	N	N
1	N	N	N	Y	N	N
2	Y	Y	N	N	N	N
3	N	Y	Y	Y	N	N
4	Y	N	N	N	N	N
5	Y	Y	Y	Y	N	N
6	Y	N	Y	N	N	N
7	Y	N	Y	Y	N	N
8	Y	Y	N	Y	N	N
9	Y	Y	Y	Y	N	N
10	N	N	N	N	N	N
11	Y	Y	Y	Y	N	N
12	N	N	N	N	N	N
13	N	N	Y	Y	N	N
14	Y	Y	Y	Y	N	N
15	N	Y	N	Y	N	N
16	Y	N	Y	Y	N	N
17	N	N	Y	Y	N	N
18	Y	Y	Y	Y	N	N
19	N	N	Y	N	N	N
20	Y	Y	Y	Y	N	N
21	Y	Y	N	Y	N	N
22	Y	Y	Y	N	N	N
23	Y	Y	Y	N	N	N
24	Y	Y	Y	Y	N	N
25	Y	Y	Y	N	N	N
Deployed	18	16	18	17	0	0
Not Deployed	8	10	8	9	26	26

4/6/22

20

## Joint Deployment Observations – CSAH 21



4/6/22

21

## Case Histories

### ➤ TH 63 (Zumbro Falls, MN)

- 5-inch thick fiber-reinforced COA on 8 to 11 inch thick HMA, constructed in 2018
- 6-foot by 6-foot panel size
- High and low air temperatures during paving were 89°F and 77°F
- Multiple 1000-foot stretches of roadway subjected to early loading
- Load vehicle: 3-axle water truck filled to two different total weights (25,000 & 58,000 lbs)
- Four passes of truck at various times and weights
- Deployment surveys done @ 1 day, 2 years

4/6/22

22

## Early Loadings

### ➤ TH 63 (Zumbro Falls, MN)

Load (lbs)	Maturity (C-hours)	Deployment
0	370	5/166
25000	720	7/166
58000	370	17/166

4/6/22

23


## Joint Deployment Observations – TH 63

7/23/2020 (Age: 2 years)					
	Segment 1	Segment 2	Segment 3	Segment 4	Segment 5
Early loading:	Yes	No	No	No	No
Panel size:	6'x6'	6'x12'	6'x12'	6'x6' with fibers	6'x6' with fibers
Joint	Northbound	Northbound	Northbound	Northbound	Northbound
1	Y	Y	Y	Y	Y
2	N	Y	Y	N	Y
3	Y	Y	Y	Y	Y
4	Y	Y	Y	Y	Y
5	Y	Y	Y	Y	Y
6	Y	Y	Y	N	Y
7	Y	Y	Y	Y	Y
8	Y	Y	Y	Y	Y
9	Y	Y	Y	Y	Y
10	Y	Y	Y	Y	Y
11	Y	Y	Y	Y	Y
12	Y	Y	Y	Y	Y
13	Y	Y	Y	Y	Y
14	N	Y	Y	Y	Y
15	Y	Y	Y	Y	Y
16	Y	Y	Y	Y	Y
17	Y	Y	Y	Y	Y
18	N	Y	Y	Y	Y
19	Y	Y	Y	Y	Y
20	Y	Y	Y	N	Y
21	N	Y	Y	N	Y
22	Y	Y		Y	
23	Y	Y		Y	
24	Y	Y			
25	Y	Y			
26	Y	Y			

4/6/22

24

## Joint Deployment Observations – TH 63



4/6/22

25

## Case Histories

### ➤ CSAH 15 (McLeod County, MN)

- 6-inch COA on variable thickness HMA, constructed in 2021
- 6-foot by 6-foot panel size
- High and low air temperatures during paving were 75°F and 52°F
- Load vehicle: 3-axle water truck filled to estimated 58,000 lbs total weight
- One pass over entire paved segment at approx. 24 hours
- Deployment surveys done @ 1 week, 5 weeks (construction traffic only)

4/6/22

26


## Joint Deployment Observations – CSAH 15

6/30/2021 (Age: 1 week)				8/9/2021 (Age: 5 weeks)		
	Segment #1		Segment #2		Segment #1	Segment #2
Joint	Southbound	Southbound	Northbound	Joint	Southbound	Southbound
0	N	N	N	0	Y	Y
1	N	N	N	1	N	N
2	N	N	N	2	Y	Y
3	Y	N	N	3	Y	Y
4	N	N	N	4	Y	Y
5	N	N	N	5	Y	N
6	N	Y	Y	6	N	Y
7	N	N	N	7	Y	N
8	N	N	N	8	N	Y
9	N	N	N	9	Y	N
10	N	N	N	10	N	Y
11	N	N	N	11	Y	N
12	N	N	N	12	N	Y
13	Y	N	N	13	Y	N
14	N	N	N	14	N	Y
15	N	N	N	15	Y	Y
16	N	N	N	16	N	Y
17	N	N	N	17	Y	N
18	N	N	N	18	N	Y
19	N	N	N	19	Y	N
20	N	N	N	20	N	Y
21	N	N	N	21	N	N
22	N	Y	Y	22	Y	Y
23	N	N	N	23	N	N
24	N	N	N	24	Y	Y
25	N	N	N	25	N	N
26	Y	N	N	26	Y	Y

4/6/22

27

## Joint Deployment Observations – CSAH 15



4/6/22

28

## Discussion

### Early loading of COA

- Experimental technique so far
- Empirical in nature
  - Variables: weather, mix design, concrete maturity, load magnitude, repetitions, axle spacing
- Results have not been consistent
- Small differences between loaded and unloaded at early age
- No clearly defined definition of success
- Does not cause visible damage to the overlay

4/6/22

29

## Conclusions

### Does it work?

- Current procedures have resulted in inconsistent results
- Highest rate of deployment has been 52% @ 1 week

**Recommendation:**  
**Discontinue procedure until**  
**a controlled research study**  
**can be carried out.**

4/6/22

30

## Questions?

**Mike Wallace**

*michael.wallace@state.mn.us*

**Tom Burnham**

*tom.burnham@state.mn.us*