# Enhancing Concrete Performance with Multi-Crystalline Enhancer (MCE) September 10, 2025

Tyson D. Rupnow, Ph.D., P.E. Associate Director, Research





#### Outline

- Background
- Laboratory Results
- Field Applications
- Questions




#### Background

- Critical Factors in Concrete Longevity
  - Design
    - Traffic, support, steel selection
  - Construction
    - Methods suited to project specifics
    - QC/QA program is a must have
  - Materials
    - Concrete durability is most important



# Background

		Workability	Transport	Strength	Cold weather	Shrinkage	Aggregate stability
Aggregate System	Type, gradation	<b>✓</b> ✓	-	-	-	-	<b>√</b> ✓
Paste quality	Air, w/cm, SCM type and dose	✓	44	<b>√</b> √	11	✓	✓
Paste quantity	Vp/Vv	✓		-	•	<b>*</b>	-






### Multi-Crystalline Enhancer (MCE)


- Crystalline water proofer
  - Enhances compressive strengths
  - Improves FT performance
  - Reduces permeability
  - Reduces ice adhesion
  - Does not change construction, curing, batching practices
- Added to fresh concrete at batching
- 2% by weight been standard



#### Laboratory Results - FT

#### IDOT C4 Mixture








### Laboratory Results - ASR

- 1567 Testing
  - IDOT C4 mixture with Platt River Aggregates





#### Water Permeability – CRD-C48-92

- TxDOT mixture proportions
- 300+ day old concrete
- 200 psi pressure differential

Cylinder ID	Coefficient of Permeability, cm/sec
4 of 12 (2% MCE)	4.985 x 10 <sup>-10</sup>
7 of 12 (2% MCE)	5.121 x 10 <sup>-10</sup>
12 of 12 (2% MCE)	4.925 x 10 <sup>-10</sup>
3 of 11 (2% MCE)	5.621 x 10 <sup>-10</sup>
7 of 11 (2% MCE)	5.195 x 10 <sup>-10</sup>
9 of 11 (Control)	2.223 x 10 <sup>-6</sup>



#### Ice Adhesion

- UT Arlington
  - Shear testing has shown a reduction of 70% in the bond strength of ice to MCE treated concrete samples



# Field Application – IDOT Slide Bridge

- Iowa Hwy 5
  - Centerville, IA
  - Lateral Slide Bridge
  - Deck placed August 4, 2023
  - Ideal Ready Mix Co.
  - IDOT C-4WR-C CL3





#### Mixture Proportions

- Type IL Cement
- Fly ash
- w/cm
- Coarse aggregate
- Sand
- WR
- MCE dosage rate

- 470 pcy
- 117 pcy
- 0.42
- 1424 pcy
- 1516 pcy
- Adjusted for site conditions
- 147 fl oz per cuyd
- "target 2% cementitious weight"



#### Water Permeability / Chloride Penetration

CRD-C48-92 @ 200 psi differential

Permeability Comparison						
Sample Designation	Age at Time of Testing	Coefficient of				
		Permeability (cm/sec)				
Control	28	6.65 x 10 <sup>-7</sup>				
MCE (Lab sample)	28	3.58 x 10 <sup>-12</sup>				
MCE (Field Trial 1)	28	3.01 x 10 <sup>-11</sup>				
MCE (Field Trial 2)	28	2.28 x 10 <sup>-11</sup>				
MCE (Field Trial 3)	28	2.61 x 10 <sup>-11</sup>				

- Nortest 492
  - Chloride migration coefficient from non-steady state migration

Sample Name	Dnssm, m <sup>2</sup> /s		
MCE1	17.314 X 10 <sup>-12</sup>		
MCE2	17.921 X 10 <sup>-12</sup>		
MCE-Pavix1	14.899 X 10 <sup>-12</sup>		
MCE-Pavix2	14.202 X 10 <sup>-12</sup>		
Control1	24.061 X 10 <sup>-12</sup>		
Control2	24.923 X 10 <sup>-12</sup>		



#### Hardened Air and Length Change


- Hardened Air Content
  - 8.74% and 8.33%
  - Spacing Factor
    - 0.082mm
  - Specific Surface
    - 36-39 mm<sup>-1</sup>

- Drying Shrinkage
  - 28-day 0.013%





# Construction







#### **Construction Summary**

- 6" slump allowed via waiver
- 270 cuyd
- Pump operator noted significantly lower pump pressures
- 7-day wet curing
- No initial surface cracking or initial distress after wet curing operations
- No surface distresses after the slide



#### Post Construction – Ice Adhesion









# Paving Project – P48

- Manatts
- MCE dosage rate 1% (0.60 gallon)
- 3/4 1" slump
- 4568 yd<sup>3</sup>
- 2 miles of pavement
- 60 sec mixing time
- 5-mile travel




# Paving Project






# Paving Project





#### Contractor Comments

- Manatts was impressed noting improved surface cream
- No issues with edges or cold joints
  - Even with a delay in truck arrival
- Project is finishing up now



# Questions



